

City of Fort Myers Procurement Services Division
Official Bid Tabulation
ITB No. 0052-23 Fencing Repairs & Replacement - Disaster
 Bid Opening Date: Tuesday, October 24, 2023 at 2:00 p.m.

McFarlane's Construction, Inc. DBA Eagle Fence Corp. 940 Country Club Blvd. Cape Coral, FL 33990	Neubert Construction Services DBA Neubert Fence & Gate 3791 Dr. MLK Jr. Blvd, Unit 3 Fort Myers, FL 33916
---	--

Item No.	Item Description	UOM	Regular Unit Price	Regular Unit Price
1	Materials (at cost, must provide documentation with invoice verifying actual cost of material)		Not Factored Into Bid	Not Factored Into Bid
2	Concrete Core Drilling for Post Installation	Each	\$100.00	\$1,500.00
3	Asphalt Core Drilling for Post Installation	Each	\$50.00	\$1,500.00
	Fence Removal Tear Down and Haul Away			
4	4-5' high Fence	Linear Foot	\$3.00	\$50.00
5	6-7' high Fence	Linear Foot	\$4.00	\$50.00
6	8-9' Fence (galvanized or vinyl coated)	Linear Foot	\$5.00	\$50.00
7	10-12' Fence (galvanized or vinyl coated)	Linear Foot	\$6.00	\$100.00
	Installation of New Fencing Material			
8	4-5' Fence (galvanized or vinyl coated)	Linear Foot	\$21.00	\$50.00
9	6-7' Fence (galvanized or vinyl coated)	Linear Foot	\$24.00	\$50.00
10	8-9' Fence (galvanized or vinyl coated)	Linear Foot	\$30.00	\$50.00
11	10-12' Fence (galvanized or vinyl coated)	Linear Foot	\$40.00	\$100.00
12	Swing Gates	Linear Foot	\$50.00	\$200.00
13	Roll Gates	Linear Foot	\$75.00	\$200.00
14	Wood Posts and Rail Fence	Linear Foot	\$24.00	\$50.00
	Installation of Class A Security Gate, <i>(include labor and accessories)</i>			
15	Powder Coated Gray	Linear Foot	\$400.00	\$500.00
16	Powder Coated Black	Linear Foot	\$400.00	\$500.00
17	Decorative Fence	Linear Foot	\$100.00	\$500.00
	Athletic Fencing			
18	Baseball Backstop Rewire, 6 gauge (up to 10' high)	Linear Foot	\$38.00	\$100.00
19	Baseball Backstop Rewire, 6 gauge (10.1'-20' high)	Linear Foot	\$76.00	\$150.00
20	Install New Backstop - 14' tall, 9 gauge galv. 2" mesh wire, 3" Line posts, 3" Term posts, (4) 1-5/8" horizontal rails, Concrete footing 48"x16" at each post.	Linear Foot	\$100.00	\$350.00
21	Install New Backstop - 20' tall, 9 gauge galv. 2" mesh wire, 3" Line posts, 4" Term posts, (5) 1-5/8" horizontal rails, Concrete footing 48"x16" at each post.	Linear Foot	\$135.00	\$500.00
22	Install New Batters Eye - 20' tall, 9 gauge galv. 2" mesh wire, 4" Line posts, 4" Term posts, (5) 1-5/8" horizontal rails, Concrete footing 48"x16" at each post.	Linear Foot	\$135.00	\$500.00
23	Additional Charge for 6" posts when fence is exposed to direct wind	Each	\$720.00	\$250.00

24	Wind Screen for Batters Eye	Linear Foot	\$4.50	\$50.00
	Welding			
25	Labor to weld, including all materials	Per Weld	\$50.00	\$500.00
Total for 1 UOM for each item			\$2,590.50	\$7,850.00
			Apparent Low Bidder	
Required Documentation				
Attachment A - Document Management Form			Yes	Yes
Attachment B - Official Bid Form in its entirety signed by an authorized principal of the company			Yes	Yes
Attachment C - Incorporation Affidavit (Notarized)			Yes	Yes
Attachment D - Byrd Anti-Lobbying			Yes	Yes
Attachment E Scope			N/A	N/A
Attachment F -Special Conditions/Bid Schedule			Yes	Yes
Attachment G - Federal Contract Provisions			N/A	N/A
Attachment H - Services Agreement - Review and Comments			Yes	Yes
Attachment I - MBE Forms (if applicable)			N/A	N/A
Licensing (Copy of Sunbiz webpage, Minority Business Enterprise License, etc.) and Certificate of Insurance			Yes	Yes
List of Subcontractors			N/A	N/A
Bidder's Notes or Alternates to SOW. List qty price breaks if applicable. Estimated use will depend on the severity and type of disaster.			Did not opt to provide, except clarified Items 2 & 3 per post, and provided additional information for Item 25: \$200 per hour.	Submitted Qty Price Breaks on a spreadsheet.

This is an unofficial copy of the tabulation of bids opened.This is not a Purchase Order.
McFarlane Construction, Inc., DBA Eagle Fence, is the apparent low-bidder.
